

BUILDING WORK

SUPPLY OF MATERIAL FOR ONE HOUSE IN CLERMONT

BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Bill No.1				
	MASONRY				
	<u>Blockwork in "Big Max" cement blocks in Class II mortar, size 390 x 190 x 140mm: (M140)</u>				
1	Blocks	No.	200		
	<u>Brickwork reinforcement</u>				
2	110mm x 20m Wide reinforcement built in horizontally.	No	1		
3	Cement original Blue NPC 32,5N 50kg	No	10		
4	Galvanized brick force 20m	No	5		
	CARPENTRY & JOINERY				
	Doors				
	<u>40mm Frame ledged, hardwood door 8 panel, hung to steel frames (elsewhere measured): (External)</u>				
5	Single door, size 813 x 2032mm high.	No	1		
	<u>40mm "Hardboard" hollow core flush panel door hung to galvanized steel frames (elsewhere measured): (Internal)</u>				
6	Single Timber Door (813 x 2032mm)	No	1		
	<u>ROOF COVERINGS</u>				
7	Galvanized Roof sheeting corrugated (686MM X 5.4M)	No	10		
8	Timber SAP SABS Rafter 38mm x 114mm x 6m	No	6		
9	Timber SAP SABS Purlins 50mm 75mm x 6m	No	6		
10	Wire Nails 5" 2 KG	No	1		
11	Wire Nails flat head 4" 2 KG	No	1		
12	Wire Nails 3" 2 KG	No	1		
13	Bracing strap 30m Roll	No	1		

	<u>IRONMONGERY</u>			
14	Three lever "CZ 69424955" mortice lockset complete with lockset and door furniture.	No	1	
	<u>METALWORK</u>			
	SUNDRY STEELWORK STEEL WINDOWS, DOORS, ETC.			
	1.2mm Thick "Durowin Type F7" residential windows complete with ironmongery, paint, etc. and fixing to brickwork or concrete:			
	Window, type NC7, size 1022 x 949mm high with glazed panel		3	
	<u>1.2mm Thick "Durowin" rebated frames suitable for 140mm wide block walls, with and including ironmongery and red oxide paint finish:</u>			
16	Frame for door 813 x 2032mm high.	No	1	
	PLASTERING AND FLOORING			
	Plaster sand(5m3)	No	1	
	PAINTWORK			
	One coat prime (White) 20L	No	1	
	PVA paint 20l cream white (Internal)	No	1	
	PVA paint 20l grey (External)	No	1	
	Carried To Section Summary			

BILL OF QUANTITIES

BILL	DESCRIPTION	PAGE		AMOUNT
	<p><u>SECTION 1 - SUMMARY</u></p> <p>1 Masonry</p> <p>2 Carpentry & Joinery</p> <p>3 Roofcoverings</p> <p>4 Ironmongery</p> <p>5 Metalwork</p> <p>6 Plastering</p> <p>7 Paintworks</p> <p>8 Delivery in Clermont:</p>			
<p>1 (A) AREA / LOCATION The unit under Ethekwini Municipality is situated in close proximity to Clermont area and the coordinate for the site location are: -29.793416, 30.906825</p>				
	<p>TOTAL TO FINAL SUMMARY</p>			

BILL OF QUANTITIES

ITEM	DESCRIPTION	PAGE			AMOUNT
	<u>FINAL SUMMARY</u>				
	Building material	1			
	Subtotal				
	ADD 15%: VAT				
	TOTAL AMOUNT				